

# PROJECT FACTS & FIGURES

---

**Project name:** SWAKOPMUND-MILE 7 WATER SUPPLY PHASE 1  
**Project code:** C-SWAM 702  
**Project area:** District of Walvis Bay, Erongo Region  
**Project objective:** Improve the reliability of the Schwartzekuppe-Swakopmund pipeline by replacing a high-risk section.

## Executing Agencies

**Planning:** Infrastructure Planning Division (NamWater)  
**Environmental Supervision:** Environmental Services (NamWater)  
**Civil Engineering Design:** Civil Design (NamWater)  
**Civil Construction:** Civil Construction (NamWater)  
**Project Management:** Fixed Asset Management (NamWater)

## Scope of Work:

Replace one section of 500 mm diameter reinforced concrete buried pipeline with 500 mm ductile cast iron (DCI) K9 above-ground pipeline complete with one in/outlet connection to the existing pipeline. The length and location of the replacement is:

- Schwartzekuppe-Swakopmund pipeline : 4 869 m (chainage: 35 496 m to 40 362 m)

**Commissioning date:** November 2009  
**Project Financing Agency:** NamWater  
**Project Cost:** N\$ 7,103,858.00 (excl. VAT)